

SQ CELSIUS LTD. (UNIT-01)
Beraiderchala, Keowa, Maona
Sreepur,Gazipur,Bangladesh.
Gazipur.
Bangladesh

Supplier
Building Care Technology Ltd
House-486, Road-32, New DOH
Mohakhali
Dhaka - 1206
Bangladesh

Purchase Order No. 114933 (Minhaz)

PO Creation Date:
Order Approved Date:

Remarks
Work Order for Civil Work with supply for Substation of SQ Celsius Unit 1.
Payment Term: 30 days credit

PO Company: SQ CELSIUS LTD.
Status: Confirmed
Delivery Start Date: 05 Apr 2021
Tax Template: Tax as per applicable law
Date In House: 11 Apr 2021

PO Division:
PO Type:
Utilization:

S.No	Article	Color	Size/Width	No. of Units	Additional Units	UOM	Uni
1.	CC Floor (CIVIL100591) 3 Thick Cement Concrete (CC) works having minimum cylinder crushing strength minimum 2200 PSI at 28 days with supply of cement (conforming to BDS 232) and coarse sand of FM 2.5 20mm down graded stone chips including screening mixing the aggregated with mixer machine casting in forms compacting by vibrator machine and curing at least for 28 days and accepted			189.0000	0.0000	S.FEET	85.C